

Visibility analysis of boundary layer transition

Original

Visibility analysis of boundary layer transition / Perrone, D.; Ridolfi, L.; Scarsoglio, S.. - In: PHYSICS OF FLUIDS. - ISSN 1070-6631. - 34:10(2022), p. 104104. [10.1063/5.0106455]

Availability:

This version is available at: 11583/2972722 since: 2022-10-31T16:57:53Z

Publisher:

AIP Publishing

Published

DOI:10.1063/5.0106455

Terms of use:

This article is made available under terms and conditions as specified in the corresponding bibliographic description in the repository

Publisher copyright

AIP postprint/Author's Accepted Manuscript e postprint versione editoriale/Version of Record

(Article begins on next page)

Visibility analysis of boundary layer transition

Cite as: Phys. Fluids **34**, 104104 (2022); <https://doi.org/10.1063/5.0106455>

Submitted: 28 June 2022 • Accepted: 15 September 2022 • Accepted Manuscript Online: 18 September 2022 • Published Online: 11 October 2022

 D. Perrone,  L. Ridolfi and  S. Scarsoglio



View Online



Export Citation



CrossMark

ARTICLES YOU MAY BE INTERESTED IN

[A comprehensive study of the onset of boundary layer separation in the unbounded flow around a circular cylinder](#)


Physics of Fluids **34**, 103607 (2022); <https://doi.org/10.1063/5.0101413>

[An open source package to perform basic and advanced statistical analysis of turbulence data and other complex systems](#)

Physics of Fluids **34**, 101801 (2022); <https://doi.org/10.1063/5.0107974>

[Deep reinforcement learning for active control of a three-dimensional bluff body wake](#)

Physics of Fluids **34**, 105126 (2022); <https://doi.org/10.1063/5.0108387>



APL Machine Learning
Machine Learning for Applied Physics
Applied Physics for Machine Learning

**First Articles
Now Online!**

Visibility analysis of boundary layer transition

Cite as: Phys. Fluids **34**, 104104 (2022); doi: [10.1063/5.0106455](https://doi.org/10.1063/5.0106455)

Submitted: 28 June 2022 · Accepted: 15 September 2022 ·

Published Online: 11 October 2022





View Online



Export Citation



CrossMark

D. Perrone,^{1,a)}  L. Ridolfi,²  and S. Scarsoglio¹ 

AFFILIATIONS

¹Department of Mechanical and Aerospace Engineering, Politecnico di Torino, 10129 Turin, Italy

²Department of Environmental, Land and Infrastructure Engineering, Politecnico di Torino, 10129 Turin, Italy

^{a)}Author to whom correspondence should be addressed: davide.perrone@polito.it

ABSTRACT

We study the transition to turbulence in a flat plate boundary layer by means of visibility analysis of velocity time-series extracted across the flow domain. By taking into account the mutual visibility of sampled values, visibility graphs are constructed from each time series. The latter are, thus, transformed into a geometrical object, whose main features can be explored using measures typical of network science that provide a reduced order representation of the underlying flow properties. Using these metrics, we observe the evolution of the flow from laminarity to turbulence and the effects exerted by the free-stream turbulence. Different from other methods requiring an extensive amount of spatio-temporal data (e.g., full velocity field) or a set of parameters and thresholds arbitrarily chosen by the user, the present network-based approach is able to identify the onset markers for transition by means of the streamwise velocity time-series alone.

Published under an exclusive license by AIP Publishing. <https://doi.org/10.1063/5.0106455>

I. INTRODUCTION

Turbulence arises from laminar fluid motion following the growth of small perturbations of the velocity profile. The interest in the study of transition is well motivated by the physical and industrial implications associated with the appearance of turbulence, which are pre-eminently linked to increased momentum transfer and drag. Important efforts in this sense are directed toward understanding, predicting, and ultimately controlling transition.

In this work, we focus our attention onto transition in the boundary layer of a flat plate with zero pressure gradient. In this setup, transition usually follows two routes. In one case, the laminar profile first develops Tollmien–Schlichting waves, whose secondary instabilities then lead to the breakdown to turbulence. In contrast to this orderly pathway, the second case occurs when turbulence in the free stream exerts a vertical forcing on the boundary layer and triggers the transition. This route is termed bypass transition and will be the focus of this work. Bypass transition takes place as follows: initially, the perturbations in the free stream generate large-scale perturbations of the streamwise velocity, i.e., streaks, inside the laminar boundary layer. Indeed, while outside the boundary layer the turbulence spectrum has a broadband nature, inside the boundary layer only low frequency perturbations appear, due to shear-sheltering. The secondary instability of streaks generates turbulent spots that are advected by the mean flow and grow in size, until their growth and merging results in the full onset of turbulence.¹

While for the orderly transition the onset of turbulence and its spatial location can be somewhat predicted and a definition of a critical

Reynolds number is usually accepted, in the case of bypass transition the problem is complicated by the chaotic nature of the forcing introduced by the free stream turbulence, so that the onset of turbulence also depends on the turbulent intensity.^{2,3} In general, the onset of turbulence is influenced by different key factors, such as the system geometry, the surface roughness, the external flow condition (most notably the pressure gradient and the already mentioned freestream turbulence). Simplified criteria have been proposed, relying on determining a critical ratio between the production term inside streamwise velocity streaks and viscous dissipation. A closely related problem to the prediction of transition is that of the determination of the spatio-temporal location of the turbulent–non-turbulent interface (TNTI). The identification of the TNTI in its simplest forms relies on the observation that certain flow field quantities usually assume different range of values in turbulent and laminar regimes.^{4–6} As such, providing an indicator function and a threshold value should, in theory, suffice to accurately discriminate between laminar and turbulent regions of the domain. Vorticity is a characterizing feature of turbulence, but its use as an indicator function is problematic due to the presence of free-stream turbulence or laminar regions where vorticity is present nonetheless, such as the streaks in the turbulent boundary layer. Other choices for the indicator function rely on the presence of velocity fluctuations to act as a discriminant between turbulent and laminar flow. A common choice in flat plate boundary layers is the sum of the wall-normal and spanwise velocity fluctuations $|v'| + |w'|$. Still, the fact that the intensity of the velocity fluctuations is strongly dependent on

the distance from the wall complicates the choice of an appropriate threshold. Methods such as Otsu's⁷ can be used to determine an appropriate threshold at different wall-normal heights, but the choice can be prone to error and an extensive knowledge of the flow field is necessary.⁸

More recently, and fueled by the increasing availability of high-resolution flow simulations and experiments, several data-driven approaches have been proposed, with the main goal of discerning the various states present in a transitional boundary layer and the key processes that govern the shift of the flow field between these states.^{9,10} Machine-learning techniques are a broad category of data analysis tools commonly employed to analyze and classify large datasets and discover underlying relations, whose application to fluid mechanics is gaining traction. Some of the most promising applications in the field of transitional flows regard the classification of flow states using unsupervised deep learning approaches. The main merit of unsupervised approaches lies in eliminating the need for *a priori* defined classifiers and/or threshold values, which are instead obtained by the learning algorithm itself. On the other hand, these approaches need extensive training on large datasets, thus requiring the knowledge of the entire velocity field and possibly also of reduction techniques to feed the unsupervised classifiers with treatable data in which the underlying relations are more easily discovered. Moreover, the very large number of parameters usually contained in a machine generated model makes somewhat difficult to obtain a clear physical interpretation of the features of classifiers, which would be useful to draw more general conclusions about the nature of the studied flow.

An alternative to data-driven approach comes from dimensional-reduction techniques that, when applied to turbulent flows, are able to extract key information from an otherwise extremely complex flow field. Along with more established methods, such as proper orthogonal decomposition, the application of techniques derived from graph theory has seen a wealth of promising applications to fluid dynamics recently.^{11,12} Graphs, or networks, are mathematical objects composed of a set of nodes and a set of the interactions entertained by the nodes; they are suited to represent large, and complex, dynamical systems, of which they can capture the essential behavior.¹³ Network-based methods have been applied to fluid flows to investigate the correlation between the velocity at different points in space¹⁴ or at different Lagrangian trajectories,^{15,16} vortical interactions,^{17,18} the proximity of particle trajectories,^{19,20} and their transition probability between subsets of the domain.^{21–23}

Time-series analysis in the context of network-based methods is particularly relevant, as the structure of time-series originating from highly complex systems is hardly captured by statistics alone. Several approaches to extract the information contained in time-series have been proposed.²⁴ Network analysis based on recurrence and on the analysis of cycles has been employed to study the transition between stable and unstable states in turbulent combustion.^{25–29} The visibility graph, which maps the steps of a time-series into the nodes of a network whose connection is determined on the basis of mutual visibility,³⁰ has been employed in the analysis of turbulence, especially for fully developed channel, boundary layer flows, and jets.^{31–35}

In this work, we apply the visibility graph to time-series extracted from a numerically simulated transitional flat plate boundary layer. The visibility graph retains the underlying structure of the process generating the time-series itself and highlights the presence of key patterns

retained by it. Moreover, the information contained inside the visibility graph can be condensed into scalar metrics using tools derived from network theory, which we will show to be sensitive to the features of time-series. Thus, we are able to identify the key elements that precede and trigger transition and to provide a thorough description of the spatial evolution of transition.

The paper is organized as follows. In Sec. II, the numerical simulation is detailed, the visibility graph method and the relevant network measures are introduced, and the properties of time-series are correlated with those of the visibility graph by means of the parametric analysis of a synthetic time-series. In Sec. III, the results are detailed, including a discussion on the application of the present method to badly resolved data. Finally, in Sec. IV concluding remarks are given.

II. METHODS

A. Transitional boundary layer dataset description

We apply the visibility graph analysis to velocity time-series extracted from a numerically simulated transitional boundary layer. The velocity fields have been made available through the John Hopkins Turbulence Database. The data are obtained via a direct numerical simulation of the flow over a flat plate of thickness $2L$ with an elliptical leading edge and a zero mean pressure gradient across the streamwise x direction. The origin ($x=0$) of the domain is located at the leading edge of the plate; this location is excluded from the stored dataset, which instead starts at approximately $x = 30L$. A sketch of the simulation domain is shown in Fig. 1. The Reynolds number Re_L based on the half-thickness of the plate, the free-stream velocity U_∞ , and the fluid viscosity ν is $Re_L = U_\infty L / \nu = 800$. The flow at the inlet is fully turbulent and is generated from a distinct simulation of homogeneous turbulence. The turbulence intensity at the inlet is about 3%, which is enough to trigger bypass transition. At the lower boundary, which is a solid wall, the no-slip condition is imposed, while along the spanwise direction periodicity is used. At the top of the domain, the boundary condition is actively controlled to satisfy continuity and keep the zero pressure gradient. The size of the domain, with respect to the plate half-thickness is $L_x \times L_y \times L_z = (969.8465 \times 26.4844 \times 240)L$, with y and z being the wall-normal and spanwise directions, respectively. The number of grid points in physical space at which the solution is stored is $N_x \times N_y \times N_z = 3320 \times 224 \times 2048$. Each time series is composed of $N_t = 4701$ time-steps for a total time stored $T = 1175L/U_\infty$; the resulting time step is $\Delta t = 0.25L/U_\infty$. A snapshot of the streamwise velocity field at $y=0.43$ is shown in Fig. 2(a). Further details on the numerical procedure employed can be found elsewhere.^{1,36,37}

B. Visibility graph and network measures

The natural visibility graph maps a discrete time-series (or an univariate function, in general) into a graph.³⁰ A graph $\mathcal{G}(\mathcal{N}, \mathcal{E})$ is an




FIG. 1. Sketch of the fluid domain. The region bounded by the dashed line indicates the stored portion of the domain.




FIG. 2. (a) Top view of the boundary layer at $y = 0.48$, $t = 0$, streamwise velocity; (b) construction of the visibility graph from a time-series and network measures. Blue points mark the sampled velocity values $u(t_i)$ and orange segments highlight the visibility links between pairs of connected nodes. Links connected to the node t_{11} are colored in green, to show an example of the degree centrality k_{11} , while the path between node t_1 and node t_{15} is highlighted in red, to highlight an example of a shortest path, $d_{1,15}$; finally, the links of the subgraph induced by nodes t_1 , t_2 , and t_3 is shown in light blue color, to show an example of the local clustering coefficient c_2 .

object comprising of a set of nodes $\mathcal{N} = \{n_1, \dots, n_N\}$ and a set of links \mathcal{E} , each one connecting a pair of nodes of the graph. A common representation of a graph is the adjacency matrix $\mathbf{A} \in \mathbb{R}^{N \times N}$, whose entries A_{ij} are equal to one if there is a connection between nodes n_i and n_j and is zero otherwise.¹³ The visibility method transforms a time-series $u(t_i)$ into a graph by assigning each time step t_i to a node and establishing a link if there is a direct line of sight between the two nodes. More specifically, two nodes i and j corresponding to time steps t_i and t_j are connected if

$$u(t_k) \leq (u(t_j) - u(t_i)) \frac{t_k - t_i}{t_j - t_i}, \quad \forall k = i, \dots, j, \quad (1)$$

where $i < j$ without loss of generality. The procedure by which links are formed between nodes is shown schematically in Fig. 2(b). Geometrically, this corresponds to creating a link between two nodes if and only if an uninterrupted straight line can be traced between the corresponding data points, without intersecting any intermediate point of the time-series. This criterion is found to preserve the properties of the time-series and to translate its features into recognizable topological structures contained in the visibility graph.³⁰

The resulting graph is fully connected (there is a path between all pair of nodes), undirected (thus having a symmetric adjacency matrix), and has a number N_t of nodes, equal to the number of steps in the time-series. The visibility graph is invariant to scale transformations of the time-series, since its links are defined following only a convexity criterion. Moreover, unlike methods such as recurrence networks, the visibility approach does not rely on parameters set by the user (such as the phase-space threshold distance in recurrence networks).

Network science adopts several metrics that, when applied to complex graphs (i.e., graphs with a large number of nodes and a non-trivial interconnection pattern), give a quick glance on the network properties. We will now enumerate the relevant network measures employed in this work and, subsequently, explain their relevance in the context of visibility analysis.

The degree centrality k_i of a node is the number of links incident to that node. Using the adjacency matrix, the degree normalized by its maximum attainable value (that is the number of nodes N) is

$$k_i = \sum_{j=1}^N \frac{A_{ij}}{N-1}. \quad (2)$$

The degree centrality is one of the most straightforward measures of centrality of a node, i.e., of its importance in the overall network structure. In Fig. 2(b), the degree centrality of two nodes is computed.

The clustering coefficient c_i is, instead, a measure of the local density of links around a node. More specifically, it expresses the probability that two neighbors of node i are themselves connected and, thus, that a connected triple of nodes is also a triangle.³⁸ It can be calculated as

$$c_i = \frac{\sum_{j,m} A_{ij} A_{jm} A_{mi}}{k_i(k_i - 1)}. \quad (3)$$

In Fig. 2(b) the computation of the clustering coefficient of the second node, c_2 , is exemplified; as its immediate neighbors form a complete graph, its clustering coefficient is equal to 1.

In order to measure the likeliness of connected nodes, it may be useful to consider the similarity of certain properties of each node of a link, i.e., the assortativity of the network. In its most basic form, the assortativity r can be measured as the Pearson correlation coefficient of the degree of the two nodes at the ends of a link, computed for all connected node pairs.^{39,40} The value of r ranges from -1 , indicating a fully disassortative network, to 1 for fully assortative networks in which connections take place only between similar (with respect to the degree centrality) nodes. As an example, nodes 11 and 12 in Fig. 2(b) (which are marked by their respective time steps, t_{11} and t_{12}) have largely different degree centralities, and thus, they contribute to make the network disassortative.

Finally, the average (or characteristic) path length L is the average length of the shortest paths connecting all pair of nodes, that is,

$$L = \frac{1}{N(N-1)} \sum_{i,j,i \neq j} d_{ij}, \quad (4)$$

where d_{ij} is the topological length of the shortest path between nodes i and j . The average path length is a measure of the typical distance

between nodes in a graph and can be used as a way to determine the effectiveness of a network in transferring information between nodes. In Fig. 2(b) the shortest path between nodes 1 and 15 is made of four links, so that $d_{1,15} = 4$; in this case, the presence of a clear peak in the time-series makes topological connection between temporally distant nodes shorter. We note that if disconnected components are present in the network, the average path length diverges; as the visibility graph is fully connected, in our case L is always bounded.

C. Visibility analysis of time-series

The application of the visibility graph formalism to time-series is known to preserve their structure, in the sense that a relation between time-series properties and those of the visibility graph can be found. As an example, periodic time-series result in regular visibility graphs, random series in random graphs, and fractal series result in graphs where scale-free features are present.³⁰ More recently, and with application to fluid dynamics, the relation between the time-series structure and network measures (as those presented before) has been explored in the context of the visibility graph.^{31–34,41,42} The main rationale behind these approaches stems from the need to provide a treatable insight on turbulent or transitional time-series, which are highly complex and need a very fine temporal resolution to be adequately represented (especially at high Reynolds numbers). By construction, the visibility graph is invariant under horizontal and vertical rescaling of the time-series; as such, the overall amplitude of the time-series has no effect on the derived network measures. On the contrary, the visibility analysis is highly sensitive to the interplay of different scales inside the time-series. As will be detailed in the following, the network measures applied to the visibility graph have the ability to convey the entity of this interplay. Finally, the visibility graph can be computed from a time-series with fast algorithms [in $\mathcal{O}(N \log N)$ time, N being the number of nodes],⁴³ which makes it suitable for use in large datasets.

To establish the properties of the visibility analysis, we now aim to show the behavior of network measures in response to the features of the time-series. To do so, we synthetically generated a time-series by superimposing three out of phase sinusoidal components of different frequency f_i and amplitude ϕ_i , a small-scale Gaussian noise and a larger amplitude Gaussian noise that has a discontinuous support (in order to mimic the intermittent behavior typical of transitional time-series). The synthetic time-series has the expression

$$u(t) = \sum_{i=\text{low,mid,high}} A_i \sin(f_i t + \phi_i) + A_{\text{noise}} w_1(t) + A_{\text{burst}} w_2(t), \quad (5)$$

where w_1 and w_2 are white Gaussian noises and w_2 is nonzero only on a fraction I of the duration of the time-series, which corresponds to the intermittency of the signal. The support for the intermittent regions of the synthetic time-series is chosen at random.

In a visibility graph, the nodes situated in large, convex portion of the time-series have a direct line of sight with a larger number of other nodes, thus having large degree. Overall, the mean degree

$$K = \frac{1}{N} \sum_{i=1}^N k_i = \frac{1}{N(N-1)} \sum_{i,j} A_{ij}, \quad (6)$$

of the visibility graph is tightly connected to the amplitude A_{low} of the lowest frequency components in the time-series, i.e., those with the largest scale. All the panels in Fig. 3 show some of the synthetic time-series used to compute the visibility graph measures. Figure 3(a) shows how the degree grows as the low-frequency component becomes more important. Indeed, the preminence of peaks spaced far apart increases the overall number of links and thus the mean degree; also, we found that the mean degree is inversely proportional to the frequency f_{low} .

The clustering coefficient also depends strongly on the local convexity of the time-series around a given node. Differently from the degree centrality, the amount of connected triples and triangles is mostly determined by the time-steps immediately adjacent to the one considered, as it is far more frequent to find connections in triples of temporally close nodes. As such, the global average

$$C = \frac{1}{N} \sum_{i=1}^N c_i \in [0, 1], \quad (7)$$

of the clustering coefficient quantifies the importance of the small-scale components of the time-series.³¹ In particular, we observe that the clustering coefficient increases as the amplitude of the small-scale Gaussian noise A_{noise} in the synthetic time-series increases [see Fig. 3(b)].

The visibility graph is also suited toward the analysis of the vertical separation, i.e., the presence of components whose amplitude is markedly different in adjacent regions of the time-series.³² gave an extended discussion regarding the ability of the assortativity coefficient r to discern between time-series whose amplitude is homogeneous over time and those that are not. In particular, when the amplitude of the time-series is homogeneous and there are no outliers, it is more probable that similar nodes are connected, leading to highly assortative networks. This behavior is of outstanding importance in the study of transitional time-series, which are strongly characterized by their intermittent behavior in the region where turbulence is not fully developed. Varying the intermittence in the synthetic time-series (that is the percentage of time, chosen at random, in which large-amplitude Gaussian noise is present) allowed us to study the behavior of the assortativity, as is shown in Fig. 3(c). The “turbulent” component is highly fluctuating, but is still somewhat homogeneous with respect to the underlying laminar component; accordingly, the assortativity is high. As the intermittency grows the network becomes increasingly assortative until the intermittency reaches unity (the series becomes fully turbulent), where the assortativity drops significantly. As already stated, the visibility graph is highly sensitive to the interplay of the different scales rather than to their actual amplitude. When the intermittency reaches unity, the laminar component disappears from the time-series and the heterogeneity of the turbulent component leads to a decrease in the assortativity.

Finally, the average path length is a measure of the topological distance between nodes; it follows easily from this consideration that the presence of localized peaks determines a decrease in the value of L , as long-distance nodes are more easily connected. As shown in Fig. 3(d), the average path length decreases when the amplitude of the temporally localized Gaussian noise in the synthetic time-series increases.

III. RESULTS

A. Network measures

We computed the visibility graph from time-series of the stream-wise velocity u from a set of points in the flow domain. In particular,




FIG. 3. Visibility parameters of the synthetic time-series: (a) average degree K with respect to the amplitude of the lowest frequency component of the time-series A_{low} ; (b) clustering coefficient C with respect to the amplitude of noise A_{noise} ; (c) assortativity r with respect to the intermittency I ; and (d) average path length L with respect to the amplitude A_{burst} of localized bursts ($I = 0.33$). Relevant time-series are plotted as insets.

for each (x, y) coordinate, we considered time-series from $N_z = 120$ equally spaced points across the homogeneous z direction of the domain. For each visibility graph, we computed the relevant network measures; in the following, we will provide results averaged along z .

Figures 3(a)–3(d) show the four visibility graph measures (K , C , r , and L) over a grid of (x, y) points that encompass the regions of the boundary layer where bypass transition takes place. Taking into account the significance of network measures in the context of the visibility graph, some features of the boundary layer can be readily identified. As stated before, the turbulent fluctuations in the boundary layer induces low-frequency, high-amplitude fluctuations of the streamwise velocity in the inner portion of the boundary layer. The degree centrality [Fig. 4(a)], which is sensitive to these low-frequency components, has a marked peak near $(x, y) = (200, 0.2)L$, where the low-frequency amplification induced by shear-sheltering appears to be at a maximum. As transition spatially progresses, the low frequency streaks encounter secondary instabilities which effectively enable the transfer of energy to smaller scales, initiating the breakdown to turbulence. Using the clustering coefficient [Fig. 4(b)], we are able to locate the start of this process at around $x = 300L$ in the innermost portion of the boundary layer, while at higher y values the high-frequency components of the time-series acquire stronger importance at higher x . Transition appears to be initiated in the innermost portion of the boundary layer. We also note that, in the region where streaks are generated, the clustering coefficient is at a minimum, as the high-frequency components of the freestream turbulence are filtered out and do not exert forcing on the boundary layer flow. Additionally, the clustering coefficient in the turbulent region of the boundary layer is slightly higher than in the free-stream, indicating some difference in

the structure of turbulence (regardless of the amplitude, which is neglected by the visibility graph).

The assortativity [Fig. 4(c)] and the average path length [Fig. 4(d)] allow us to investigate the intermittent behavior of the time-series just before full transition occurs. As already stated, these time-series are characterized by the passage, in fixed points of the domain, of turbulent spots. As x grows, the size and frequency of spots grows and, accordingly, the intermittency of the time-series grows. The remarkable ability of the assortativity to distinguish between intermittent time-series (even with high intermittency values) and fully turbulent ones allows us to identify a region, located prior to the fully developed turbulent boundary layer, where intermittency is at a maximum (but still not unity). This region with high assortativity presents itself as an almost vertical front located at around $x = 380L$, which is followed by a decrease in assortativity. We hypothesize that the region of maximum assortativity is the region which hosts the turbulent-non turbulent interface. The average path length has a maximum in the streaky region, where the low-frequency fluctuations of the streamwise velocity present no clear, localized peak. Instead, there is a minimum at around $x = 300L$ and very low y values. The minimum indicates that time-series in this region present localized peaks and a somewhat reduced intermittency (the assortativity is also very low in the same region, indicating a strongly heterogeneous time-series). It is interesting to note that at slightly higher x coordinates the strong increase in the clustering coefficient takes place; indeed, it is the expansion and coalescence of localized spots that generates complete transition to turbulence.

Figure 4(e) shows three time-series extracted from the corresponding, color-coded, points indicated in Figs. 4(a)–4(d) and at




FIG. 4. Visibility graph measures in the transitional boundary layer: (a) Average degree, (b) clustering coefficient, (c) assortativity, and (d) average path length. The boundary layer height δ_{99} is shown in black, while the average position of the TNTI $\bar{x}_{\text{TNTI}}(y)$ is shown in red. Panel (e) shows three time-series sampled at the corresponding, color-coded points of the domain; the spanwise coordinate is $z = 13.95$ for all time-series. Below each time-series, the corresponding visibility graph is drawn by a force-directed algorithm.

$z = 13.95$ and, below, the corresponding visibility graph plotted with a force-directed algorithm.⁴⁴ The leftmost time-series is taken from the region of the domain in which turbulent spots are present. Here the presence of peaks, which are also evident in the graph plot as single nodes connected with large, separate clusters, contributes to the low value of L , while the presence of laminar regions determines the high value of K . To better identify these large clusters we applied the Louvain partitioning algorithm⁴⁵ and computed the average size of communities. In the case of the leftmost time-series, the average cluster comprises 522 nodes. In the central time-series and in its corresponding graph plot, taken near the turbulent-non turbulent interface

where the assortativity r is at a maximum, the hub-spoke organization typical of the spotty time-series is less evident, but clusters still appear visibly larger than in the fully turbulent case due to the contribution of persistent low frequency components (the average cluster size is 204); consequently, the degree is also slightly larger with respect to that of the fully turbulent time-series. Finally, in the rightmost time-series, taken from a region where turbulence is fully developed, the size of clusters is much smaller (on average, they comprise 130 nodes). Conversely, here the clustering coefficient is at a maximum as the high-frequency components are predominant.

To further complement our results, we added to the plots in Fig. 4 the boundary layer height δ_{99} (black curves), which is the y coordinate at which the streamwise average velocity is 99% the freestream velocity, and an approximate location of the TNTI (red curves). To find the location of the turbulent-non turbulent interface across the wall-normal coordinate y we used the procedure proposed by.⁸ In particular, for each time step of the boundary layer simulation data and at each wall-normal height, we applied Otsu's method⁷ to the sum of the wall-normal and spanwise velocity fluctuations $|v'| + |w'|$ in order to obtain a threshold value (as a function of y and t). Otsu's method is an image segmentation technique that identifies the optimal threshold of a scalar value (the grayscale in images or $|v'| + |w'|$ in the boundary layer). In particular, the method achieves the objective of minimizing the intra-class variance within the turbulent and the laminar regions, and does so by maximizing the inter-class variance between the laminar and turbulent regions. Because of the dependence on y of the wall-normal velocity fluctuations, a global (y -independent) threshold cannot be provided and Otsu's procedure has to be applied to isolated vertical slices of the boundary layer flow, as prescribed by.⁸ After we obtained the spatial profile of the TNTI as a surface $x_{\text{TNTI}}(y, z, t)$ at different times we averaged the results along time and along z to obtain an expected average profile of the TNTI, $\bar{x}_{\text{TNTI}}(y)$.

First, we note that the variation of the network measures takes place inside the boundary layer, at y coordinates lower than δ_{99} , while in the free-stream the measures remain mostly stationary. Moreover, the expected position of the turbulent-non turbulent interface using Otsu's thresholding is clearly superimposable to the regions where network measures signal the transition to fully developed turbulence. In particular, the region of maximum assortativity and the TNTI intersect in a wide range of y coordinates, indicating that the assortativity measures, as was hypothesized before, incipient transition. It is also worth noting that the spike of the clustering coefficient in the innermost region of the boundary layer is located slightly before the expected location of the interface, possibly indicating that to some extent the transfer of energy to smaller scales precedes full transition.

B. Sensitivity analysis

We now aim to assess the response of the visibility analysis to the decrease in spatial and temporal resolution. In particular, we will provide results that are averaged along a reduced number of points along z and results obtained using subsampled time-series. The analysis of subsampled time-series is relevant because it may provide useful insight in the analysis of data with lower resolution, such as experiments having sparser data acquisition setup or LES simulations over complex 3D geometries.

Panels from Fig. 5(a) show the network measures averaged using only 10 points along z (instead of $N_z = 120$ used previously); we also plotted the location of the TNTI computed using Otsu's method and its standard deviation along z (dashed lines). The overall trends of the measures across the domain are preserved. In particular, a peak of the assortativity is still present near the transition region, making this measure suitable for a local determination of the TNTI. Network properties do not change significantly along the homogeneous direction of the domain.

Figures 5(b) and 5(c) show the network measures obtained from subsampled time-series. Starting from the full time-series, comprising of N_t time-steps, we constructed the subsampled time-series by taking

one out of Δ points, so that $u_i^\Delta = u_{\Delta i}$. We thus obtained subsampled time-series which are effectively deprived of the highest frequency components. The effect of the subsampling from the perspective of the visibility graph is a result of both the elimination of a fraction of the original data and of the reduction in the number of nodes.

In Fig. 5(b), the four network measures (K , C , r , and L) obtained from a subsampled time-series with $\Delta = 5$ are shown. The degree centrality has been normalized with the correct number of nodes, which is N_t/Δ . Even if 80% of the original information contained in the time-series is lost, the visibility measures of the subsampled time-series are tightly related to those of the full ones. All the previously identified spatial patterns are preserved through the subsampling. The degree centrality is left mostly unchanged, as the subsampling procedure affects only slightly the larger timescale in the time-series (which are the ones that influence the degree centrality); moreover, the decrease in the number of nodes can be fully accounted for by normalization. The clustering coefficient, while retaining the previously found spatial trends (most notably, the presence of a minimum around $x = 200$), increases everywhere in the domain. While the removal of the high-frequency components triggers a decrease in the clustering coefficient at a fixed number of time-steps [see Fig. 3(b)], this seems to not be the case when the number of time-steps is decreased. Moreover, it appears that the increase in the clustering coefficient has the same magnitude in regions of the domain where the time-series are dominated by either low- or high-frequency components, indicating that the reduction of the number of nodes has the most prominent effect on the visibility graph structure. The assortativity appears to be slightly reduced everywhere, although not by much. Moreover, the spatial location of its maximum, which we correlated with the location of the TNTI, appears to be located at slightly lower x coordinates. We hypothesize that this is due to the loss of information occurring because of the subsampling, which makes it impossible to distinguish a time-series with a high value of the intermittency I from a fully turbulent one. Finally, the average path length L diminishes everywhere as the lesser number of nodes is correlated with a reduction of the shortest path lengths. Around $x = 200$ the average path length of the full time-series presents a peak, which is progressively smoothed as the subsampling parameter Δ increases. In that region of the domain the dynamics of the flow is dominated by low-frequency streaks and turbulent spots are mostly yet to appear, which, in the fully sampled case, leads to high values of L . It appears that fine-structure changes like those induced by the subsampling considerably affect the structure of the visibility graph obtained from time-series of streaky flow.

The panels of Fig. 5(c) show the network measures at a fixed wall-normal coordinate ($y = 0.98$) and two different subsampling parameters, $\Delta = 2$ and 5. With $\Delta = 2$, even if half the information of the original time-series is lost, the network properties behave in a similar manner to the fully sampled ones. In particular, we note that the assortativity r is mostly unchanged and the peak is located at the same x -location as in the fully sampled case. Moreover, a peak of L in the streaky region is still present, indicating that the effects of the subsampling with $\Delta = 2$ are mostly due to the halving of the number of nodes.

We performed the same analysis at higher values of Δ (up to $\Delta = 20$) obtaining a progressive loss of quality in the network measures. This is indeed expected, as the loss of information due to the subsampling inevitably reflects on the quality of the visibility graph analysis.




FIG. 5. (a) Degree, clustering coefficient, assortativity, and average path length of the visibility graph at a fixed spanwise coordinate ($z = 13.95$); black lines indicate the values of δ_{99} , while the red lines the average position of the TNTI and the dashed red lines its standard deviation along z . (b) Measures for networks obtained from subsampled time-series with $\Delta = 5$ (results are now averaged along $N_z = 120$ points in the spanwise direction). (c) Network measures from the subsampled time-series at $y = 0.98$ with different values of the subsampling parameter Δ (again, results are averaged along $N_z = 120$ points).

Nonetheless, if the sampling guarantees that all the relevant scales of the flow are retained, the qualitative behavior of the results obtained through the visibility graph is independent from the exact value of the sampling rate.

IV. CONCLUSIONS

We performed a visibility analysis on time-series obtained from a numerically simulated transitional boundary layer. After characterizing the behavior of network measures using a parametric time-series, we computed these measures for the visibility graphs obtained from

streamwise velocity time-series extracted from the flow domain. The four metrics, namely, the degree centrality K , the clustering coefficient C , the assortativity r , and the average path length L are together able to accurately provide a view on the spatial evolution of the bypass transition from laminar to turbulent flow, as they encode the interplay of scales and the transformations occurring due to the onset of turbulence.

Most notably, we found that the assortativity r , i.e., the Pearson correlation coefficient between the degree of linked pair of nodes, has a peak in the region of the domain immediately preceding the rise of

developed turbulence and is thus able to act as a reliable onset marker for transition. This finding is noteworthy since the visibility analysis does not require any *a priori* parameter and, most importantly, because an extensive knowledge of the velocity field is not needed. Indeed, our results are obtained from the streamwise component u of the velocity and from single point measurements only. To identify a time-averaged location of the TNTI using the present approach, one would only need to compute the assortativity coefficient of visibility graph from different x coordinates at a fixed wall-normal height y and spanwise coordinate z and find the location of the peak of r . Our approach provides results in agreement with more established methods, such as those based on thresholding physical quantities through Otsu's algorithm, but does not need the same extensive knowledge of the flow field of these methods. Although the thresholding of the indicator function $|v'| + |w'|$ provides a time-instantaneous location of the TNTI, it requires the knowledge of the velocity field on at least a slab of the domain at constant wall-normal height with reasonable resolution. Moreover, we found that similar results are obtained using sub-sampled time-series, confirming the robustness of the method with incomplete data.

The visibility graph methodology appears suited toward the analysis of flows with abrupt changes in their dynamics. Accordingly, the current approach can be applied in future works to investigate the influence of key factors influencing transition to turbulence (such as geometry, wall roughness, pressure gradient). Moreover, the visibility approach could be extended to respect temporal causality by including a directional information into the link definition, thus creating a directed graph. Past research has shown how this allows the visibility graph to detect time-series generated by irreversible process and could be useful to identify and quantify the arising of irreversibility due to transition to turbulence.⁴⁶ Overall, network-based methods have an interesting outlook with regard to application in fluid dynamics, as they are able to capture the interplay of scales typical of turbulent, highly complex flows and provide meaningful and consistent results when applied to highly different cases, such as the laminar, intermittent, and turbulent portions of a transitional boundary layer flow.

ACKNOWLEDGMENTS

Computational resources were provided by HPC@POLITO, a project of Academic Computing within the Department of Control and Computer Engineering at the Politecnico di Torino (<https://www.hpc.polito.it>).

AUTHOR DECLARATIONS

Conflict of Interest

The authors have no conflicts to disclose.

Author Contributions

Davide Perrone: Conceptualization (equal); Data curation (lead); Investigation (equal); Software (lead); Writing – original draft (equal); Writing – review & editing (equal). **Luca Ridolfi:** Conceptualization (equal); Investigation (equal); Supervision (equal); Writing – original draft (equal); Writing – review & editing (equal). **Stefania Scarsoglio:** Conceptualization (equal); Investigation (equal); Supervision (equal); Writing – original draft (equal); Writing – review & editing (equal).

DATA AVAILABILITY

Data sharing is not applicable to this article as no new data were created or analyzed in this study. All numerical simulation data are available online through the John Hopkins Turbulence Database.

REFERENCES

- ¹T. A. Zaki, "From streaks to spots and on to turbulence: Exploring the dynamics of boundary layer transition," *Flow, Turbul. Combust.* **91**, 451–473 (2013).
- ²O. Vermeerschand D. Arnal, "Klebanoff-mode modeling and bypass-transition prediction," *AIAA J.* **48**, 2491–2500 (2010).
- ³S. Bhushan, D. K. Walters, S. Muthu, and C. L. Pasilio, "Identification of bypass transition onset markers using direct numerical simulation," *J. Fluids Eng.* **140**, 111107 (2018).
- ⁴K. R. Sreenivasan and C. Meneveau, "The fractal facets of turbulence," *J. Fluid Mech.* **173**, 357–386 (1986).
- ⁵K. Chauhan, J. Philip, C. M. de Silva, N. Hutchins, and I. Marusic, "The turbulent/non-turbulent interface and entrainment in a boundary layer," *J. Fluid Mech.* **742**, 119–151 (2014).
- ⁶G. Borrell and J. Jiménez, "Properties of the turbulent/non-turbulent interface in boundary layers," *J. Fluid Mech.* **801**, 554–596 (2016).
- ⁷N. Otsu, "A threshold selection method from gray-level histograms," *IEEE Trans. Syst., Man, Cybern.* **9**, 62–66 (1979).
- ⁸K. P. Nolan and T. A. Zaki, "Conditional sampling of transitional boundary layers in pressure gradients," *J. Fluid Mech.* **728**, 306–339 (2013).
- ⁹F. Foroozan, V. Guerrero, A. Ianiro, and S. Discetti, "Unsupervised modelling of a transitional boundary layer," *J. Fluid Mech.* **929**, A3 (2021).
- ¹⁰Z. Wu, J. Lee, C. Meneveau, and T. Zaki, "Application of a self-organizing map to identify the turbulent-boundary-layer interface in a transitional flow," *Phys. Rev. Fluids* **4**, 023902 (2019).
- ¹¹G. Iacobello, L. Ridolfi, and S. Scarsoglio, "A review on turbulent and vortical flow analyses via complex networks," *Physica A* **563**, 125476 (2021).
- ¹²K. Taira and A. G. Nair, "Network-based analysis of fluid flows: Progress and outlook," *Prog. Aerosp. Sci.* **131**, 100823 (2022).
- ¹³S. Boccaletti, V. Latora, Y. Moreno, M. Chavez, and D.-U. Hwang, "Complex networks: Structure and dynamics," *Phys. Rep.* **424**, 175–308 (2006).
- ¹⁴S. Scarsoglio, G. Iacobello, and L. Ridolfi, "Complex networks unveiling spatial patterns in turbulence," *Int. J. Bifurcation Chaos* **26**, 1650223 (2016).
- ¹⁵K. L. Schlueter-Kuck and J. O. Dabiri, "Coherent structure colouring: Identification of coherent structures from sparse data using graph theory," *J. Fluid Mech.* **811**, 468–486 (2017).
- ¹⁶P. P. Vieweg, C. Schneide, K. Padberg-Gehle, and J. Schumacher, "Lagrangian heat transport in turbulent three-dimensional convection," *Phys. Rev. Fluids* **6**, L041501 (2021).
- ¹⁷K. Taira, A. G. Nair, and S. L. Brunton, "Network structure of two-dimensional decaying isotropic turbulence," *J. Fluid Mech.* **795**, R2 (2016).
- ¹⁸C.-A. Yeh, M. Gopalakrishnan Meena, and K. Taira, "Network broadcast analysis and control of turbulent flows," *J. Fluid Mech.* **910**, A15 (2021).
- ¹⁹I. I. Rypina and L. J. Pratt, "Trajectory encounter volume as a diagnostic of mixing potential in fluid flows," *Nonlinear Processes Geophys.* **24**, 189–202 (2017).
- ²⁰R. Banisch, P. Koltai, and K. Padberg-Gehle, "Network measures of mixing," *Chaos* **29**, 063125 (2019).
- ²¹E. Ser-Giacomi, V. Rossi, C. López, and E. Hernández-García, "Flow networks: A characterization of geophysical fluid transport," *Chaos* **25**, 036404 (2015).
- ²²D. Perrone, J. G. M. Kuerten, L. Ridolfi, and S. Scarsoglio, "Wall-induced anisotropy effects on turbulent mixing in channel flow: A network-based analysis," *Phys. Rev. E* **102**, 043109 (2020).
- ²³D. Perrone, J. G. M. Kuerten, L. Ridolfi, and S. Scarsoglio, "Network analysis of Reynolds number scaling in wall-bounded Lagrangian mixing," *Phys. Rev. Fluids* **6**, 124501 (2021).
- ²⁴R. V. Donne, M. Small, J. F. Donges, N. Marwan, Y. Zou, R. Xiang, and J. Kurths, "Recurrence-based time series analysis by means of complex network methods," *Int. J. Bifurcation Chaos* **21**, 1019–1046 (2011).
- ²⁵V. Godavarthi, V. R. Unni, E. A. Gopalakrishnan, and R. I. Sujith, "Recurrence networks to study dynamical transitions in a turbulent combustor," *Chaos* **27**, 063113 (2017).

- ²⁶P. Kasthuri, I. Pavithran, S. A. Pawar, R. I. Sujith, R. Gejji, and W. Anderson, "Dynamical systems approach to study thermoacoustic transitions in a liquid rocket combustor," *Chaos* **29**, 103115 (2019).
- ²⁷S. Tandon and R. I. Sujith, "Condensation in the phase space and network topology during transition from chaos to order in turbulent thermoacoustic systems," *Chaos* **31**, 043126 (2021).
- ²⁸Y. Nomi, H. Gotoda, S. Fukuda, and C. Almarcha, "Complex network analysis of spatiotemporal dynamics of premixed flame in a Hele-Shaw cell: A transition from chaos to stochastic state," *Chaos* **31**, 123133 (2021).
- ²⁹T. Hachijo, H. Gotoda, T. Nishizawa, and J. Kazawa, "Early detection of cascade flutter in a model aircraft turbine using a methodology combining complex networks and synchronization," *Phys. Rev. Appl.* **14**, 014093 (2020).
- ³⁰L. Lacasa, B. Luque, F. Ballesteros, J. Luque, and J. C. Nuno, "From time series to complex networks: The visibility graph," *Proc. Natl. Acad. Sci.* **105**, 4972–4975 (2008).
- ³¹G. Iacobello, S. Scarsoglio, and L. Ridolfi, "Visibility graph analysis of wall turbulence time-series," *Phys. Lett. A* **382**, 1–11 (2018).
- ³²G. Iacobello, M. Marro, L. Ridolfi, P. Salizzoni, and S. Scarsoglio, "Experimental investigation of vertical turbulent transport of a passive scalar in a boundary layer: Statistics and visibility graph analysis," *Phys. Rev. Fluids* **4**, 104501 (2019).
- ³³S. Chowdhuri, G. Iacobello, and T. Banerjee, "Visibility network analysis of large-scale intermittency in convective surface layer turbulence," *J. Fluid Mech.* **925**, A38 (2021).
- ³⁴G. Iacobello, L. Ridolfi, and S. Scarsoglio, "Large-to-small scale frequency modulation analysis in wall-bounded turbulence via visibility networks," *J. Fluid Mech.* **918**, A13 (2021).
- ³⁵W. Kobayashi, H. Gotoda, S. Kandani, Y. Ohmichi, and S. Matsuyama, "Spatiotemporal dynamics of turbulent coaxial jet analyzed by symbolic information-theory quantifiers and complex-network approach," *Chaos* **29**, 123110 (2019).
- ³⁶Y. Li, E. Perlman, M. Wan, Y. Yang, C. Meneveau, R. Burns, S. Chen, A. Szalay, and G. Eyink, "A public turbulence database cluster and applications to study Lagrangian evolution of velocity increments in turbulence," *J. Turbul.* **9**, N31 (2008).
- ³⁷E. Perlman, R. Burns, Y. Li, and C. Meneveau, "Data exploration of turbulence simulations using a database cluster," in *SC '07: Proceedings of the 2007 ACM/IEEE Conference on Supercomputing* (IEEE, 2007), pp. 1–11.
- ³⁸D. J. Watts and S. H. Strogatz, "Collective dynamics of 'small-world' networks," *Nature* **393**, 440–442 (1998).
- ³⁹M. E. J. Newman, "Assortative mixing in networks," *Phys. Rev. Lett.* **89**, 208701 (2002).
- ⁴⁰M. E. J. Newman, "Mixing patterns in networks," *Phys. Rev. E* **67**, 026126 (2003).
- ⁴¹M. Murugesan and R. Sujith, "Combustion noise is scale-free: Transition from scale-free to order at the onset of thermoacoustic instability," *J. Fluid Mech.* **772**, 225–245 (2015).
- ⁴²J. Singh, R. Belur Vishwanath, S. Chaudhuri, and R. I. Sujith, "Network structure of turbulent premixed flames," *Chaos* **27**, 043107 (2017).
- ⁴³X. Lan, H. Mo, S. Chen, Q. Liu, and Y. Deng, "Fast transformation from time series to visibility graphs," *Chaos* **25**, 083105 (2015).
- ⁴⁴S. Martin, W. M. Brown, R. Klavans, and K. W. Boyack, "OpenOrd: an open-source toolbox for large graph layout," in *Visualization and Data Analysis 2011*, International Society for Optics and Photonics, edited by P. C. Wong, J. Park, M. C. Hao, C. Chen, K. Börner, D. L. Kao, and J. C. Roberts (SPIE, 2011), Vol. 7868, pp. 45–55.
- ⁴⁵V. D. Blondel, J.-L. Guillaume, R. Lambiotte, and E. Lefebvre, "Fast unfolding of communities in large networks," *J. Stat. Mech.* **2008**, P10008.
- ⁴⁶L. Lacasa, A. Nunez, É. Roldán, J. M. Parrondo, and B. Luque, "Time series irreversibility: A visibility graph approach," *Eur. Phys. J. B* **85**, 1–11 (2012).